Ironbark Home Repair

ESTIMATE

100 Example Road
Cedar Valley, ST 00000
(555) 010-4477
estimates@example.com
Fictional business - demonstration only

NUMBER	EST-2026-0142
ISSUED	September 26, 2026
VALID UNTIL	October 26, 2026

PREPARED FOR

Sample Customer
200 Sample Lane
Cedar Valley, ST 00000
customer@example.com

PROJECT

Rear deck repair and refinish
200 Sample Lane (rear yard)
Replace damaged decking and stair treads, reinforce the railing, then clean, stain and seal the full deck (approx. 240 sq ft).

DESCRIPTION	QTY	UNIT	RATE	AMOUNT
Structural inspection Check joists, ledger and footings; photo report before work starts. (non-taxable)	1	ea	$0.00	$0.00
Remove & replace deck boards Pressure-treated 5/4x6, approx. 18 boards, fasteners included.	18	board	$27.50	$495.00
Stair tread replacement 3 steps, 2 treads each.	6	tread	$34.00	$204.00
Railing reinforcement New post anchors and blocking at 4 posts.	4	post	$65.00	$260.00
Clean, stain & seal Deck wash, brightener, semi-transparent stain, 2 coats.	240	sq ft	$2.15	$516.00
Labor - carpentry (non-taxable)	14.5	hr	$68.00	$986.00
Debris haul-away (non-taxable)	1	ea	$85.00	$85.00

Subtotal	$2,546.00
Off-season scheduling discount	-$75.00
Tax 8.25% on $1,431.55	$118.10
Total	**$2,589.10**
Deposit to schedule (30%)	**$776.73**

NOTES

Price assumes joists and ledger are sound. If the inspection finds hidden damage, we stop and send a written change estimate before any extra work.

TERMS

1. This estimate is valid until the date shown above.
2. A 30% deposit schedules the work; the balance is due on completion and walkthrough.

DEMONSTRATION

3. Materials are itemized; any substitution is agreed in writing first.
4. Weather delays are rescheduled at no extra cost.

ACCEPTANCE

Signing below approves the scope and price above. Work is scheduled once the deposit is received.

Accepted by (name & signature) _____ Date _____

DEMONSTRATION